

# PA-32-260 CHEROKEE SIX

## FLOW + VERIFY CHECKLIST (POH-ALIGNED)

**Aircraft:** PA-32-260 Cherokee Six

**Tail Number:** N563VW

**Engine:** Lycoming O-540-E4B5

### IFR PERFORMANCE PROFILES

| Phase            | Power      | Pitch      | Config | Speed                      | V/S      |
|------------------|------------|------------|--------|----------------------------|----------|
| Takeoff          | FULL       | +8 to +10° | 10°    | 65 MPH rotate / 105 MPH Vy | +800 fpm |
| Climb            | FULL       | +7°        | CLEAN  | 105 MPH                    | +800 fpm |
| Cruise           | ~15 in MP  | 0°         | Clean  | —                          | —        |
| Descent          | Low / Idle | −2 to −3°  | Clean  | 138 MPH                    | −500 fpm |
| Approach Level 1 | ~15 in MP  | 0 to −1°   | 25°    | 104 MPH                    | −500     |
| Approach Level 2 | ~17 in MP  | 0°         | 33°    | 104 MPH                    | −800     |
| Missed           | FULL       | +7°        | Clean  | 97 MPH                     | +800     |

## NORMAL OPERATIONS

### □ INITIAL STARTUP

#### FLOW

Brakes — SET

Flaps — UP

Electrical — OFF

Circuit Breakers — ALL IN

Propeller — FULL FORWARD

Throttle — 1/4" OPEN

Carb Heat — OFF

Battery / Master — ON

Fuel Pump — ON

Prime — 2-3 STROKES / AS REQUIRED

Primer — LOCKED

Fuel Selector — PROPER TANK

Mixture — RICH

Prop Area — CLEAR

Engine Start — ENGAGE

Oil Pressure — CHECK

Avionics Master — ON

Throttle — SET 1000 RPM

#### VERIFY

Radios / GPS — POWERED / READY

Annunciators — CHECKED

### PREFLIGHT / TAXI

*Style: Heading 2 (Green icon prefix)*

## **FLOW**

Fuel Quantity — CHECK / PROPER TANK

Oil — CHECK

Controls — FREE / CORRECT

Flight Instruments — SET / NO FLAGS

Documents / Charts — ON BOARD / CURRENT

Garmin 530W Database — CURRENT / IFR LEGAL

Garmin 530W Flight Plan — LOADED / VERIFIED

Trim — SET TAKEOFF

Brakes — CHECK

Avionics — AS REQUIRED

Taxi — CLEAR / CONTROLLED

## **VERIFY**

Attitude Indicator — ERECT / NO TUMBLE

Heading Indicator — ALIGNED / SET

Turn Coordinator — ALIVE / RESPONDS

Altimeter — SET / CROSS-CHECKED

CDI / OBS — IDENT / SET

Suction — IN GREEN / STABLE

Transponder — SET / ALT MODE

COM / NAV Radios — SET / IDENTIFIED

## **RUN-UP / BEFORE TAKEOFF**

*Style: Heading 2*

## **FLOW**

Parking Brake — SET

Throttle — 2000 RPM

Engine Gauges — GREEN

Magnetos — CHECK (within limits)

Carburetor Heat — CHECK → OFF

Propeller Pitch — CYCLE 3 TIMES / –300 RPM MAX

Suction — CHECK

Throttle — IDLE / SMOOTH

## **VERIFY**

Stable RPM

No abnormal vibration

Engine indications normal

## **TAKEOFF / CLIMB**

### **FLOW**

Fuel Pump — ON

Lights — AS REQUIRED

Flaps — SET

Power — SET TAKEOFF POWER

Engine Gauges — GREEN / FULL POWER

Airspeed Alive — CHECK

Rotate — **65 MPH**

Climb Power — SET / VERIFY

Climb — **Vy 105 MPH**

## **INSTRUMENT FLIGHT RULES (IFR)**

### **IFR — DEPARTURE / ENROUTE**

#### **FLOW**

Clearance — REVIEW (route / altitude / frequencies)

Bugs — HDG / ALT / MINs SET

Navigation Source — CONFIRM

Instruments — CHECK (gyro / CDI sensing)

Fuel Pump — ON

Lights — AS REQUIRED

#### **VERIFY**

Garmin 530W Database — CURRENT / APPROVED

Garmin 530W Flight Plan — ACTIVE / CROSS-CHECKED

CDI Source — GPS / VLOC AS REQUIRED

Approach Frequency — SET / MONITOR

### **GARMIN 530W IFR QUICK CONFIG**

Power Up — SELF TEST / NO FLAGS

Database Page — CHECK / CURRENT

Flight Plan — LOAD / ACTIVATE

CDI Source — GPS OR VLOC / VERIFY

OBS Mode — SET / RESET AS REQUIRED

Approach — SELECT / BRIEF

Comms / Nav — CROSS-CHECK / IDENT

Procedures — LOAD / VERIFY

### **IFR — APPROACH CONFIGURATION**

#### **IN-RANGE**

Plate Brief — DSCRAM

Communications — SET / MONITOR

Missed Approach — REVIEW / BRIEF

6 Ts — CYCLE / CONFIRM

DADS — BRIEF / CONFIRM

### **PRE-FAF**

BCGUMPFS — BRIEF / CONFIRM

Course Interception — SET / VERIFY

Course Alive — CALL / VERIFY

Glideslope Alive — CALL / VERIFY

Groundspeed — VERIFY / TREND

6 Ts — CHECK / CONFIRM

DADS — CHECK / CONFIRM

### **FAF**

Power — SET

Pitch — SET

Configuration — FLAPS \_\_\_\_°

Airspeed — \_\_\_\_ MPH

Sink Rate — \_\_\_\_ FPM

DA / DH / MDA — CALL OUT

DADS — EVERY 500 FT

Missed Approach — CALL OUT / EXECUTE AS REQUIRED

*Goal: Stabilized by FAF*

## **MISSED APPROACH (MEMORY ITEMS)**

### **IMMEDIATE ACTIONS**

- **Power** — FULL
- **Pitch** — +7°
- **Configuration** — CLEAN
- **Airspeed** — 97 MPH
- **Climb** — +800 fpm

## **LANDING / GO-AROUND**

### **Landing — FLOW**

Airspeed — AS REQUIRED

Flaps — AS REQUIRED

### **Go-Around — FLOW**

Power — FULL

Carb Heat — OFF

Flaps — RETRACT IN STAGES

Airspeed — ≥95 MPH

## ☐ SHUTDOWN

### FLOW

Avionics Master — OFF

Lights — OFF AS REQUIRED

Mixture — IDLE CUTOFF

Throttle — IDLE

Magnetos — OFF

Master — OFF

Fuel Selector — OFF

### VERIFY

Engine Secured

Keys Removed / Aircraft Secure

## EMERGENCY & ABNORMAL OPERATIONS

### CRITICAL MEMORY ITEMS

*(Always accessible)*

Engine Failure — **100 MPH**

Engine Fire (In-Flight) — **Mixture IDLE CUTOFF**

Electrical Fire / Smoke — **MASTER OFF**

### ENGINE FAILURE — IN FLIGHT

#### FLOW

Airspeed — **100 MPH (BEST GLIDE)**

Fuel Selector — FULLEST TANK

Fuel Pump — ON

Mixture — FULL RICH

Carb Heat — ON

Throttle — OPEN

#### VERIFY

Power restored → Resume normal operations

### ENGINE RESTART — IN FLIGHT (POH)

#### FLOW

Fuel Selector — FULLEST

Fuel Pump — ON

Mixture — FULL RICH

Carb Heat — ON

Throttle — 1" OPEN

Magnetos — BOTH

Primer — AS REQUIRED

Engine Gauges — CHECK

## **FORCED LANDING**

### **FLOW**

Airspeed — **100 MPH**  
Landing Site — SELECT  
Mixture — IDLE CUTOFF  
Fuel Selector — OFF  
Fuel Pump — OFF  
Magnetos — OFF  
Master — OFF  
Seatbelts — SECURE  
Door — UNLATCH  
Flaps — AS REQUIRED

## **ENGINE FIRE — IN FLIGHT**

### **FLOW**

Mixture — IDLE CUTOFF  
Fuel Selector — OFF  
Fuel Pump — OFF  
Magnetos — OFF  
Cabin Heat / Air — OFF  
Airspeed — **125 MPH (TOP WHITE ARC)**  
→ Proceed to **Engine Failure / Forced Landing**

## **ELECTRICAL FIRE / SMOKE (POH-ALIGNED)**

### **FLOW**

Master Switch — OFF  
All Electrical Switches — OFF  
Cabin Heat — OFF  
Air / Vents — OPEN (ventilate)

### **VERIFY**

Smoke dissipating

### **IF ELECTRICAL POWER REQUIRED**

Master — ON  
Essential Circuits — ON **ONE AT A TIME**  
If smoke returns:  
→ Master OFF → **Land ASAP**

## **ALTERNATOR FAILURE / NO CHARGE**

### **FLOW**

Electrical Load — REDUCE  
Alternator Field CB — CHECK / RESET  
Alternator Output CB — CHECK / RESET

Alternator — OFF (30 sec) → ON

## **VERIFY**

Ammeter shows system load

If no output:

➔ Alternator OFF → Minimal load → **Land ASAP / Practical**